

# TRAILERING

*checklist*

## TRAILER SETUP CHECK

Check your trailer setup

- Trailer sits level behind tow vehicle
- Hitch ball size is correct
- Coupler is fully secured
- Safety chains are attached
- Trailer jack is completely raised

## PRE-TRIP WALKAROUND

Walk your trailer before departure every single time for safety.

- Tire Pressure
- Lug Nuts
- Trailer Lights & Turn Signals
- Bow Strap
- Safety Chain
- Transom Straps
- Bimini Top
- Board Racks (if equipped)

## BOAT LAUNCH STAGING

Prepare your boat before backing down the ramp in a staging area.

- Insert all plugs
- Verify the drive is trimmed appropriately (if applicable)
- Remove transom straps
- Load gear
- Prepare dock lines
- Get passengers ready

## BEFORE BACKING DOWN:

Prepare your boat before backing down the ramp in a staging area.

- Make sure you're using the correct launch lane (if applicable)
- Double-check all plugs are installed
- Back down slowly and carefully

## CALL YOUR SERVICE DEPARTMENT FOR SUPPORT

### BELLEVUE | NEWPORT

425.641.2090

[newport\\_service@seattleboat.com](mailto:newport_service@seattleboat.com)

### SEATTLE | LAKE UNION

206.633.2628

[seattle\\_service@seattleboat.com](mailto:seattle_service@seattleboat.com)

### KENT

253.872.8192

[kent\\_service@seattleboat.com](mailto:kent_service@seattleboat.com)

### LAKE TAPPS

253.891.0762

[tapps\\_service@seattleboat.com](mailto:tapps_service@seattleboat.com)